

Financial Bid

NIT No. IGIDR/Tender/2026/ED/12

Date: 03.07.2026

**Tender Name: External Repair, Waterproofing, & painting works of Multiple Buildings, and
Construction of New Washrooms near the Administrative Block at IGIDR**

SUMMARY OF THE FINANCIAL BID

Sr. No.	Work Details	Total Amount INR
1	External Repair, Waterproofing, & painting works of Multiple Buildings at IGIDR	
2	Construction of New Washrooms near the Administration Block at IGIDR	
	TOTAL AMOUNT WITH GST INR	

Total quoted amount, including GST in words, Rupees..

Date:

Signature and Stamp of the Bidder

** The financial bid should be submitted on the company letterhead with signature and stamp on it.*

Financial Bid

NIT No. IGIDR/Tender/2026/ED/12

Date: 03.07.2026

Tender Name: External Repair, Waterproofing, & painting works of Multiple Buildings, and Construction of New Washrooms near the Administrative Block at IGIDR

PART-I: External Repair, Waterproofing, & painting works of Multiple Buildings at IGIDR										
S.N.	Item Description	Buildingwise Quantity						Unit	Rate ₹	Total Amount ₹
		Admin	Seminar Rooms	Cafeteria	Guest House	New Hostel	Total Quantity			
1	Waterproofing Treatment to terrace by using Polymeric Cementitious Membrane as approved by Engineer in charge, followed by 112mm thick brick bat coba covered with 20 mm mortar finish. If there are cracks on the bare slab, open the crack in V Groove and fill it with ready to use repair polymer modified mortar based on special cements, aldehyde based polymers with thixotropy modifying agents. If there are lots of honeycombs and identified bad patches of concrete the same should be grouted as per the instructions of site incharge. (The grouting shall be paid separately). Clean the entire surface thoroughly and over this prepared surface, apply three coats of polymeric Cementitious waterproofing coating having a non-toxic, 2-(methoxycarbonyl)-1-propene-Butyl-2 propenoate (MPBP) based polymeric waterproofing solution as approved by Engineer in charge. Provide and lay 112 mm average thicknes of brick bat coba in cement mortar 1:5 over 12mm thick CM 1:3 bedding with one pouch of 330 grams of thorough blend of special cements, aldehyde based polymers, shrinkage compensating agents as approved by Engineer in charge per 50 Kg bag of cement and finishing with 20 mm thick cement plaster in cement mortar 1:3 by mixing one 330 grams pouch of above admixture per 50 Kg bag of cement, including all lead, lifts and laid to proper slope to drain off water entirely preparing bell mouth including watta, beveled or champhered portion at the junction of parapet and work up to a height of 300 mm or as directed and including finishing the top layer of waterproofing treatement with false marking of 30 cm x 30 cm or as directed, curing and covering the whole treatment. MPBP Polymeric Waterproofing Coating for Concrete and Masonry should have following minimum properties: (1) Elongation % (ASTM D412-2016): @ 100% (2) Tensile Strength N/mm2 (ASTM D412-2016): 3.3 (3) Specific Gravity: 1.02 ± 0.02 (4) Total Solids (ASTM D1644-2012): 43.98 (5) Hardness Shore A (ASTM D2240-2015): 82	223.00	525.00	170.00	1680.00		2598.00	Sqm		

PART-I: External Repair, Waterproofing, & painting works of Multiple Buildings at IGIDR										
S.N.	Item Description	Buildingwise Quantity						Unit	Rate ₹	Total Amount ₹
		Admin	Seminar Rooms	Cafeteria	Guest House	New Hostel	Total Quantity			
2	Removing the tar or coba and disposing of the material as directed etc. complete.	763.00	1125.00	170.00	1780.00	0.00	3838.00	Sqm		
3	Providing and laying jointless Polydee-LM, a highly flexible elastometric coating for RCC / cementitious surface for terrace waterproofing on B.B. Coba / R.C.C, after application of TP- 42 Primer on perfectly clean surface (free from loose dust and foreign matter) application of 1st coat of Polydee-LM @ 700 gms/ One Square Metre and applying 2nd coat of Polydee-LM @ 700 gms/ One Square Metre and finishing the same with sprinkling the AG-10 granules on the wet coating. (After finishing covering the treatment with 25mm cement plaster for protection with fibrillated 6mm Plyplast fibre @ 125 gms/ One Square Metre.) covering 7 years guarantee on Court Fee Stamp Paper of Rs. 100/- etc. complete. For Semicircular Surfaces (Extra for 25 mm cement plaster added in rate)	540.00	600.00		100.00		1240.00	Sqm		
4	China mosaic terrace waterproofing involving preparing the surface, applying a 1:4 cement-sand mortar bed, and then laying and grouting the china mosaic tiles with a waterproof or water-resistant sealant. The cost to include creating a 20-25mm thick mortar bed with a proper slope, ensuring a joint width of 3-5mm, and a final curing period of at least 3-15 days. The gaps between the china chips should be about 3-5 mm. After initial curing, raked out the joints if necessary and fill them with a waterproof cement slurry or a white/colored cement slurry for the desired aesthetic	540.00	600.00	0.00	100.00	0.00	1240.00	Sqm		

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

PART-I: External Repair, Waterproofing, & painting works of Multiple Buildings at IGIDR										
S.N.	Item Description	Buildingwise Quantity						Unit	Rate ₹	Total Amount ₹
		Admin	Seminar Rooms	Cafeteria	Guest House	New Hostel	Total Quantity			
26	Providing and applying two coats of synthetic enamel paint of approved colour to new /old structural steel work and wood work in buildings, including scaffolding if necessary, cleaning and preparing the surface etc. complete.	50.00	50.00	50.00	100.00	200.00	450.00	Sqm		
	TOTAL BASIC AMOUNT WITHOUT GST INR									
	Add GST @ 18% AMOUNT INR									
	TOTAL AMOUNT WITH GST INR									

Total quoted amount including GST in words, Rupees..

Date:

Signature and Stamp of the Bidder

* The financial bid should be submitted on the company letterhead with the signature and stamp on it.

Financial Bid**NIT No. IGIDR/Tender/2026/ED/12****Date: 03.07.2026****Tender Name: External Repair, Waterproofing, & painting works of Multiple Buildings, and Construction of New Washrooms near the Administrative Block at IGIDR**

PART-II: Construction of New Washrooms near the Administration Block at IGIDR					
SR. NO.	ITEM DESCRIPTION	QUANTITY	UNIT	RATE ₹	AMOUNT ₹
1	Excavation for foundation in Hard murum and boulders including removing the excavated material upto a distance of 50 metres, beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift from 1.5 m to 3.0 m.) By Mechanical Means.	45.00	Cum		
2	Providing preconstructional antitermite treatment as per I.S. 6313 (Part-II) by treating the bottom surface and sides of excavation at the rate of 5 litres of emulsion concentrate of 1.0 percent of chlorophyrifos per square meter of surface area covering 10 years guarantee on bond paper.	135.00	Sqm		
3	Providing preconstructional antitermite treatment as per I.S. 6313 (Part-II) by treating the top surface of plinth filling at the rate of 5 litres of emulsion concentrate at 1.0 percent of clorophyrifos per One Square Metre of surface area covering ten years guarantee on bond paper.	20.00	Sqm		
4	Filling in plinth and floors with approved excavated material in 15cm. to 20cm. Layers including watering and compacting etc. complete.	33.00	Cum		
5	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete.	3.00	Cum		
6	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.	5.00	Cum		
7	Providing soling using 80 mm size trap metal in 15 cm. layer including filling voids with Crushed sand/grit, ramming, watering etc. complete.	3.00	Cum		

PART-II: Construction of New Washrooms near the Administration Block at IGIDR					
SR. NO.	ITEM DESCRIPTION	QUANTITY	UNIT	RATE ₹	AMOUNT ₹
8	Providing structural steel work in hollow section of various thickness and sizes in square, rectangular and round shape from 25mm to 450mm section as per IS 4923 YST 310 Grade produced from iron ore and blast furnace route etc. as per detailed designs and drawing or as directed including cutting, fabricating, hoisting, erecting, fixing in position, making riveted/bolted/ welded connections and painting complete.	0.50	MT		
9	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete. With fine aggregate (Crushed sand VSI Grade)	6.00	Cum		
10	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for foundation and bedding / steps including steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.) complete. With fine aggregate (Crushed sand VSI Grade)	3.00	Cum		
11	Providing and laying Cast in situ/Ready Mix cement concrete in M20 of trap/ granite/quartzite/gneiss metal for steps including steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.) complete. With fine aggregate (Crushed sand VSI Grade)	3.00	Cum		

PART-II: Construction of New Washrooms near the Administration Block at IGIDR					
SR. NO.	ITEM DESCRIPTION	QUANTITY	UNIT	RATE ₹	AMOUNT ₹
12	Providing and laying Cast in situ/Ready Mix cement concrete M-30 of trap / granite/quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. columns as per detailed designs and drawing or as directed including Steel centering formwork, cover blocks laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel). complete. With fine aggregate (Crushed sand VSI Grade)	6.00	Cum		
13	Providing and laying Cast in situ/Ready Mix cement concrete M-25 of trap / granite /quartzite/ gneiss metal for R.C.C. columns as per detailed designs and drawings or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete,(Excluding reinforcement and structural steel) complete. With fine aggregate (Crushed sand VSI Grade)	3.50	Cum		
14	Providing and laying Cast in situ/Ready Mix cement concrete in M-25 of trap/ granite/ quartzite/ gneiss metal for R.C.C. beams and lintels as per detailed designs and drawings or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction and roughening the surface if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel). complete. With fine aggregate (Crushed sand VSI Grade)	7.00	Cum		
15	Providing and laying Cast in situ/Ready Mix cement concrete M-25 of trap/ granite / quartzite/ gneiss metal for R.C.C. slabs and landings as per detailed designs and drawings including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc complete,(Excluding reinforcement and structural steel). complete. With fine aggregate (Crushed sand VSI Grade)	4.00	Cum		

PART-II: Construction of New Washrooms near the Administration Block at IGIDR					
SR. NO.	ITEM DESCRIPTION	QUANTITY	UNIT	RATE ₹	AMOUNT ₹
16	Providing and laying Cast in situ/Ready Mix cement concrete M-25 of trap/ granite/ quartzite/ gneiss metal for R.C.C. chajja as per detailed design and drawings including steel centering, formwork, cover blocks, laying/pumping, compacting and roughening the surface if special finish is to be provided and curing complete. (Excluding reinforcement and structural steel). complete. With fine aggregate (Crushed sand VSI Grade)	0.75	Cum		
17	Providing and laying Cast in situ/Ready Mix cement concrete in M-25 of trap/ granite/ quartzite/ gneiss metal for R.C.C. pardi of required thickness including steel centering, formwork, cover blocks, laying/pumping, compacting and roughening them if special finish is to be provided and curing complete. (Excluding reinforcement and structural steel). complete. With fine aggregate (Crushed sand VSI Grade)	3.50	Cum		
18	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.	3.50	MT		
19	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually, striking joints on unexposed faces, raking out joints on exposed faces and watering etc. Complete.	2.00	Cum		
20	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete	20.00	Cum		
21	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:4 in half brick thick wall including mild steel longitudinal reinforcement of 2 bars of 6 mm diameter / 2 hoop iron strips 25 mm X 1.6 mm placed at every third course, properly bent and bonded at ends scaffolding, raking out joints and watering etc. complete.	21.00	Sqm		

PART-II: Construction of New Washrooms near the Administration Block at IGIDR					
SR. NO.	ITEM DESCRIPTION	QUANTITY	UNIT	RATE ₹	AMOUNT ₹
22	Providing expansion joints in R.C.C. framed structure (at terrace level) with premoulded filler 25 mm thick and 3 mm thick aluminium plate as required, bituminous poured filler, fixing lead, flashing on upper side and T.W. battens on inner face finishing etc. Complete as directed.	4.00	Sqm		
23	Providing and laying damp proof course 50 mm thick in M20 cement concrete layer and bitumen / using cement with waterproofing compound curing, formwork etc. complete.	5.00	Sqm		
24	Providing cement based water proofing treatment to terraces (Indian water proofing or alike) with brick bats laid in required slope to drain the water for any span after cleaning the base surface. Applying a coat of cement slurry admixed with approved water proofing compound and laying the brick bats on bottom layer in C.M.1:5 admixed with approved water proofing compound filling up to half depth of brick bats, curing this layer for 3 days, applying cement slurry over this layer joints of brick bats with C.M.1:3 admixed with approved water proofing compound and finally top finishing with average 20 mm. thick layers of same mortar added with jute fiber at 1Kilogramper bag including finishing the surface smooth with cement slurry admixed with approved water proofing compound. Marking finished surface with false squares of 300mm x 300 mm. making the junctions at the parapet rounded and tapered top for required height, with drip mould at the junction of plaster and parapet and curing and covering 10 years Guarantee against leakproofness on Court fee stamp paper of Rs. 500/- including ponding test etc. complete.	26.00	Sqm		
25	Providing waterproofing in W.C. and bath including brick bat coba in all position including providing and laying 12mm bedding in cement mortar 1:3 on vergin concrete slab with waterproofing compound @ 1Kilogram/per bag of cement laying brick bat coba of required thickness in cm 1:5 with waterproofing compound 1 Kilogram/bag of cement grouting and finishing the top layer with 20mm thick brick bedding in cm mortar 1:3 with waterproofing compound 1 Kilogram/per bag of cement and testing the treated portion for 48 hours by pond test and covering ten years' guarantee on requisite stamp paper including curing etc. complete.	6.00	Cum		

PART-II: Construction of New Washrooms near the Administration Block at IGIDR					
SR. NO.	ITEM DESCRIPTION	QUANTITY	UNIT	RATE ₹	AMOUNT ₹
26	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1Kilogramper cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.	170.00	Sqm		
27	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:3 without neeru finish to concrete or brick surfaces, in all position including scaffolding and curing etc. complete.	150.00	Sqm		
28	Providing and fixing machine cut mirror polished 18 mm to 20 mm thick telephone black granite / Amba White / Cat bary brown / RBI red / Ocean Brown granite stone partition with full moulding the edges etc. complete . Both side polish	2.00	Sqm		
29	Providing and laying vitrified mirror / glossy finish tiles having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10 mm thickness and confirming to IS. 15622-2006 (group Bla) of approved make, shade and pattern for dado and skirting in required position fixed in 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. complete	100.00	Sqm		
30	Providing and laying vitrified matt fininsh tiles having size 590 mm to 605 mm x to 605 mm of 8 to 10 mm thickness and confirming IS. 15622-2006 (Group Bla) of approved make, shade and pattern for flooring in required position laid on a bed of 1:4 cement morar including neat cement float, filling joints, curing and cleaning etc. complete.	21.00	Sqm		
31	Providing and applying pearl/ luster finish paint of approved colour and shade to the existing plaster surface including scaffolding, preparing the surface, applying the acrylic wall putti etc.	50.00	Sqm		

PART-II: Construction of New Washrooms near the Administration Block at IGIDR					
SR. NO.	ITEM DESCRIPTION	QUANTITY	UNIT	RATE ₹	AMOUNT ₹
32	Providing and applying two coats of exterior weather shield paint of approved manufacture and of approved colour to the plastered surfaces including cleaning ,preparing the plaster surface ,applying primer coat ,scaffolding if necessary, and watering the surface for two days etc complete. NOTE: For Item One Number 15 to 18 prior approval of Superintending Engineer will be necessary	170.00	Sqm		
33	Providing and fixing solid core flush door shutter in single leaf 32 mm thick decorative type of exterior grade as per detailed drawings approved face veneers 3 mm thick on both faces or as directed, all necessary beads, mouldings and lipping, wrought iron hold fasts, chromium plated fixtures and fastenings, with brass mortise lock, chromium plated handles on both sides, and finishing with French Polish etc. complete.	4.20	Sqm		
34	Providing and fixing 34 mm thick moulded door shutter consisting of solid core single leaf flush door of 30 mm thickness lipped with 15 mm (5mm x 3) thick x 30 mm width on one style and top rail and 10 mm (5mm x 2) thick x 30 mm width on other style and bottom rails. The inner panels laminated with 2 mm thick termite proof, water proof and fire resistant moulded PVC sheet with 2,4,6 design in different plain and /or prelim colours on one side after routing the moulded design on flush doors and 2 mm plain and /or pre lam PVC on other side using rubber adhesive on flush door and solvent cement adhesive on the PVC lipping etc. as per direction of Engineer in charge and manufacturers specification and drawing etc. complete.	8.40	Sqm		
35	Providing and fixing in position anodised (as per IS 1868/1982) Aluminium fixed staggered (Z Type) Ventilator with aluminium rectangular pipe 63 mm x 38.10 mm x 1.22 mm at weight 0.650 Kilogram/One Running Metre, Aluminium angle of size 15 mm x 15 mm x 1 mm,aluminium channel of 9 mm sizes, S.S.mosquito net of 304 Grade,4 mm thick float glass per detailed drawing and as directed by Engineer in charge etc.complete.	5.04	Sqm		
36	Providing and fixing mild steel grill work for windows, ventilators, etc. 15 Kilogram/ One Square Metre as per drawing including fixtures necessary welding and painting with one coat of anticorrosive paint and two coats of oil painting complete.	5.04	Sqm		

PART-II: Construction of New Washrooms near the Administration Block at IGIDR					
SR. NO.	ITEM DESCRIPTION	QUANTITY	UNIT	RATE ₹	AMOUNT ₹
37	Providing and fixing screw down for 32 mm dia. wheeled stop tap of brass including necessary sockets/union nut complete.	2.00	Nos		
38	Providing and fixing White Glazed Earthenware full stall type Urinal with P.V.C. flushing cistern of 5 liters capacity with fitting, inlet pipes and stop tap, brackets for fixing the cistern, 32 mm dia. P.V.C flush pipe with fittings and flushing arrangement including lead soil pipe, lead trap, soil pipe connection up to the outside face of the wall	2.00	Nos		
39	Providing and fixing 15cm x 10cm salt glazed stoneware gully trap in cement concrete 1:4:8 outside the building including cast iron grating in the sink, connecting glazed stoneware pipe, brick masonry chamber with cast iron lid and cast iron grating for the gully trap.	1.00	Nos		
40	Providing and laying concrete pipes of I.S.NP. class of 225mm diameter in proper line, level and slope including necessary collars, excavation, laying, fixing with collars in cement mortar 1:1 and refilling the trench complete.	10.00	Rm		
41	Providing and constructing Brick Masonry Inspection Chamber 60cm x 45cm x 90cm including 1:4:8 cement concrete foundation 1:2:4 cement concrete channels half round G.S.W. pipes, Brick Masonry, plastering from inside and airtight C. I. cover of 75Kilogram with lid and frame fixed in cement concrete.	1.00	Nos		
42	Providing and fixing 450mm x 550mm size superior type Belgium mirror with 16mm dia. nickel plated towel rod etc.	5.00	Nos		
43	Providing, laying and fixing P.V.C. pipe of 50mm dia. with fittings such as bends, tees, reducers, clamps, etc. including necessary excavation, trench filling etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	10.00	Rm		
44	Providing and fixing 75 mm dia stabiliser pipe/ P.V.C. soil vent/waste pipe and with necessary fixtures and fitting such as bends, tees, single junctions, slotted vent, clamps etc. complete	20.00	Rm		
45	Providing and fixing 100 mm dia stabiliser pipe/ P.V.C. soil vent/waste pipe and with necessary fixtures and fitting such as bends, tees, single junctions, slotted vent, clamps etc. complete.	20.00	Rm		

PART-II: Construction of New Washrooms near the Administration Block at IGIDR					
SR. NO.	ITEM DESCRIPTION	QUANTITY	UNIT	RATE ₹	AMOUNT ₹
46	Providing and fixing on walls/ ceiling/ floor 15 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	30.00	Rm		
47	Providing and fixing on walls/ceiling/floor 20 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	30.00	Rm		
48	Providing and fixing on walls/ ceiling/ floor 25 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	30.00	Rm		
49	Providing and fixing on walls/ ceiling/ floor 32 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	30.00	Rm		
50	Providing and fixing 10 cm PVC nahani trap with grating etc. complete.	8.00	Nos		
51	Providing and fixing C.P. Angular stop clock with wall flange of approved make continental including necessary sockets/union nut etc. complete.	12.00	Nos		
52	Providing and fixing C.P.Two way BIB cock of approved make continental including necessary sockets/union nut etc. complete.	5.00	Nos		

PART-II: Construction of New Washrooms near the Administration Block at IGIDR					
SR. NO.	ITEM DESCRIPTION	QUANTITY	UNIT	RATE ₹	AMOUNT ₹
53	Providing and fixing P.V.C. Rain water pipes of 110mm outer diameter and having wall thickness of 2.2 to 2.7 mm confirming to I.S. 13592-1992 including proper rainwater receiving recess with P.V.C. plug, bend, necessary fittings, such as, offsets, shoes, including fixing the pipe on wall using approved wooden cleats projecting 25mm to 40mm from face of wall a fixing with clips of approved quality and One Number ,filing the joint using rubber gasket with solvent cement and properly resting the shoe of pipes on C.C. or masonry blocks, including necessary scaffolding and maintenance for 3 yrs for any leakages or dislocations of pipes. All the P.V.C. fittings and additional 2 piece socket clips shall be got approved from engineer in charge etc. complete.	6.00	Rm		
54	Providing and fixing oval type under counter wash hand basin of 16 inch x 22 inch size and of special colour shade having telephonic black / coloured granite of 180 mm thick stone black kadappa framework including chromium plated coupling bottle - Trap using CERA company or equivalent oval tupa wash basin model no 3448 as per detailed drawing or as directed by engg incharge etc complete. (Counter size 1.20 m x 0.60 m)	5.00	Nos		
55	Providing and fixing European type white glazed earthenware water closet pan with UPVC seat and lid with chromium plated brass hinges and rubber buffers including UPVC and vent pipe up to the outside face of wall 10 litre enameled low level flushing cistern with fittings pipe stop tap brackets for fixing cistern 32 mm dia. UPVC flush pipe with fittings and clamps ,20 mm dia.UPVC overflow pipe ,mosquito proof couplings G.I. chain and pulley,with water Jet and fitting including cutting and making good to the walls and floors testing etc. complete.	5.00	Nos		
56	Point wiring for light/bell/exhaust fan in 20 mm FRLS grade HMS PVC conduit with 1.5 sq.mm (2+1E) FRLSH grade copper wire, modular type switch, earthing and required accessories. Average length of point 10 meters	8.00	Nos		
57	Point wiring for ceiling/ exhaust fan in 20 mm FRLS grade HMS PVC conduit with 1.5 sq.mm (2+1E) FRLSH grade copper wire, modular type switch, earthing and required accessories. Average length of point 10 meters	7.00	Nos		

PART-II: Construction of New Washrooms near the Administration Block at IGIDR					
SR. NO.	ITEM DESCRIPTION	QUANTITY	UNIT	RATE ₹	AMOUNT ₹
58	Point wiring for independent plug in 20 mm FRLS grade HMS PVC conduit with 1.5 sq.mm (2+1E) FRLSH grade copper wire, modular type switch, earthing and required accessories	4.00	Nos		
59	Secondary point wiring for additional light/ bell point, concealed type in min 20 mm FRLS grade PVC conduit with 1.5 sq.mm. (2+1E) FRLSH grade copper wires with required accessories. Average length of point 3 meters	4.00	Nos		
60	Wiring for secondary plug on board with Switch socket surface/concealed type, copper wiring and earthing and with modular accessories	4.00	Nos		
61	Supplying and erecting mains with 3x2.5 sq.mm FRLSH copper PVC insulated wire laid in provided conduit/trunking/inside pole/Bus bars or any other places	40.00	Rm		
62	Supplying and erecting LED square / circular Max. 18 W down lighter/Panel Light having pressure die-cast aluminium housing, polystyrene diffuser having system lumens output of Min. 2000 Lumens, min. efficacy of 110 lumen/W, CRI>80, CCT upto 6500K, Beam Angle of 120 deg., max. ripple of 5%, THD<10%, p.f. >0.95, operating range of 120-270V, surge protection of 2.5 kV, Life class of 50,000 Hrs. at L70B50, including driver, having mounting arrangement with board for surface type or spring loaded mounting clips complete with 3 years warranty.	12.00	Nos		
63	Supplying, erecting & marking SPMCB 6A to 32A, C-series with rated short -circuit breaking capacity (Icn) 10kA in provided distribution board	6.00	Nos		
64	Supplying and erecting fresh air cum exhaust fan of light duty 250 V A.C. 50 cycles 300mm. 1400 RPM rust proof body & blades, wire mesh, duly erected, complete.	7.00	Nos		
65	Supplying, erecting & marking DPMCB 6A to 32A, C-series with rated short -circuit breaking capacity (Icn) 10kA in provided distribution board.	1.00	Nos		

PART-II: Construction of New Washrooms near the Administration Block at IGIDR					
SR. NO.	ITEM DESCRIPTION	QUANTITY	UNIT	RATE ₹	AMOUNT ₹
66	Supplying and erecting single pole and neutral distribution board (SPNDB), with 2 ways for incoming and 6 ways (6 poles) for outgoing SP MCBs, with door, 1.2mm thickness surface / flush mounted, IP 43 Protection on iron / GI frame.	1.00	Nos		
67	Supplying and erecting mains with 3x4 sq.mm FRLSH copper PVC insulated wire laid in provided conduit/trunking/inside pole/Bus bars or any other places	50.00	Rm		
	TOTAL BASIC AMOUNT WITHOUT GST INR				
	Add: GST @ 18% AMOUNT INR				
	TOTAL AMOUNT WITH GST INR				

The Total quoted amount including GST in words Rupees..

Date:

Signature and Stamp of the Bidder

** The financial bid should be submitted on the company letterhead signature and stamp on it.*