## **FINANCIAL BID**

## NIT No: IGIDR/Tender/2020/ED/05 Date:12th February 2020

Schedule of Rates for Supply, Installation, Testing and commissioning of Indoor Split AC units at IGIDR Campus

SR. NO.	DESCRIPTION	Unit	Qty.	Unit Rate	Amount (A)	GST %	GST Amount (B)	Total Amount (A+B)
Α	Part A- Supply of Split Air-Conditioners:				•			` ,
1	Supply of Split type HIghWall Airconditioners comprising Indoor Unit, Outdoor unit, isolating valves, thermostatic control, safety cutouts, (condensor mounting stand excluded) and vibration isolation pads. Specify Make -							
а	SPLIT AC - 1.5 TR 3 Star rated, Model:	Nos.	12.00					
b	SPLIT AC - 2.0TR 3 Star rated, Model:	Nos.	1.00					
С	SPLIT AC - 1.0TR 3 Star rated, Model:	Nos.	1.00					
	Total for Supply (All Inclusive & GST @18%) (A) Rs.							
В	Part B- Installation, charging and commissioning of Split Air-Conditioners:							
1	Installation, charging and commissioning of the Hiwall systems with the R-410A refrigerant for the above stated machines as per the specs. This shall include the nitrogen leak testing, oil charging, vaccumisation and other accessories as per the specs- Gas Charging, Lifting Shifting etc. complete.							
а	SPLIT AC - 1.5 TR 3 Star rated	Nos.	12.00					
b	SPLIT AC - 2.0TR 3 Star rated	Nos.	1.00					
С	SPLIT AC - 1.0TR 3 Star rated	Nos.	1.00					
2	Installation and Commissioning of hard/soft copper Refrigerant piping of standard size with PUF insulation, complete with fittings, elbows, bends, supporting arrangement on walls, cable trays/trenches.							
а	SPLIT AC - 1.5 TR 3 Star rated	Rmt.	110.00					
b	SPLIT AC - 2.0TR 3 Star rated	Rmt.	10.00					
С	SPLIT AC - 1.0TR 3 Star rated	Rmt.	7.00					
3	Electrical Cabling from Indoor to Outdoor							
	Supply & installation of electrical cabling to connect IDU power supply. Electrical Flexible Copper cabling Polycab make, including saddle, end terminations, necessary hardware, etc.							
а	3 Core x 2.5 Sq.mm	Rmt.	75.00					
	Supply, Fabrication and Installation of MS base frame for Indoor & Outdoor units complete with epoxy painting, vibration isolation pads, supports, hangers, railing, brackets etc.							
	SPLIT AC - 1.5 TR 3 Star rated	Nos.	12.00					
	SPLIT AC - 2.0TR 3 Star rated	Nos.	1.00					
С	SPLIT AC - 1.0TR 3 Star rated	Nos.	1.00					
5	Drain Piping							
а	Supply and installation of drain piping PVC hard pipes of suitable size, with fitting, accessories, bends, elbows, tees, flanges, tappings, wall sleeves, hangers, supports, anchors.	Rmt.	60.00					
6	Core cutting of required size provided with PVC sleeve pipe including proper closing of holes in wall.	Nos.	1.00					
<b>-</b>	Diamonthing of evicting and exit AC units		4					
7	Dismantling of existing old split AC units	Nos.	14.00					
	Total for Installation (All Inclusive & GST @18%) (B) Rs.							
	Grand Total Amount (A+B) Rs.							
_			4					
С	Less:- Buy Back Price for 14 Nos. old existing Split Units Rs.	Nos.	14.00					
	Total Quoted Amount with Buy Back Offer All Inclusive Rs.							

## Note:-

2) All the Taxes are included.

Signature & seal of bidder Date: