

## FINANCIAL BID

### UPGRADATION OF INFRASTRUCTURAL FACILITIES IN IGDR, GOREGAON.

Quotation for Supply, Installation and commissioning of Interior Guest house single Room-18 ( Part-IV) Split AC Work (Phase-3), in the campus.

| SR. NO.  | DESCRIPTION  | QUOTED AMOUNT (WITH GST) |        |               |                  |        |                |                           |
|----------|--|--------------------------|--------|---------------|------------------|--------|----------------|---------------------------|
|          |  | Unit                     | Qty.   | Unit Rate Rs. | Basic Amount Rs. | GST %  | GST Amount Rs. | Total Amount with GST Rs. |
| <b>A</b> | <b>Part A- Supply of Split Air-Conditioners:</b>   |                          |        |               |                  |        |                |                           |
| 1        | Supply & Installation of Split type HighWall Airconditioners comprising Indoor Unit, Outdoor unit, isolating valves, thermostatic control, safety cutouts, (condensor mounting stand excluded) and vibration isolation pads. Make model-HITACHI(TOUSHI) 3 STAR         |                          |        |               |                  |        |                |                           |
| a        | SPLIT AC - 1.0TR HITACHI 3 STAR RATED (TOSUHI 3100F -RSF312HBDW)   | Nos.                     | 1.00   |               | -                | 28.00% | -              | -                         |
| b        | SPLIT AC - 1.5TR HITACHI 3 STAR RATED (TOUSHI 3100S -RSH318HBDW)   | Nos.                     | 17.00  |               | -                | 28.00% | -              | -                         |
|          | <b>TOTAL FOR SUPPLY AMOUNT (A)</b>   |                          |        |               | -                |        | -              | -                         |
| <b>B</b> | <b>Part B- Installation, charging and commissioning of Split Air-Conditioners:</b>   |                          |        |               |                  |        |                |                           |
| 1        | Installation, charging and commissioning of the Hiwall systems with the R-22 refrigerant for the above stated machines as per the specs. This shall include the Gas leak testing and other accessories as per the specs- Gas Charging, Lifting Shifting etc. complete. |                          |        |               |                  |        |                |                           |
| a        | 1.0TR Hiwall unit 3 Star rated   | Nos.                     | 1.00   |               | -                | 18.00% | -              | -                         |
| b        | 1.5TR Hiwall unit 3 Star rated   | Nos.                     | 17.00  |               | -                | 18.00% | -              | -                         |
| 2        | Installation and Commissioning of hard/soft copper Refrigerant piping, complete with fittings, elbows, bends, supporting arrangement on walls, cable trays/trenches.   |                          |        |               |                  |        |                |                           |
| a        | 1.0TR Hiwall unit 3 Star rated   | Rmt.                     | 12.00  |               | -                | 18.00% | -              | -                         |
| b        | 1.5TR Hiwall unit 3 Star rated   | Rmt.                     | 210.00 |               | -                | 18.00% | -              | -                         |
| 3        | <b>Electrical Cabling from Indoor to Outdoor</b><br>Supply & installation of electrical cabling to connect IDU power supply. electrical Flexible cabling Polycab make, including saddle, end terminations, necessary hardware, etc.                                    |                          |        |               |                  |        |                |                           |
| a        | 3 Core x 2.5 Sq.mm   | Rmt.                     | 230.00 |               | -                | 18.00% | -              | -                         |
| 4        | <b>Supply and Installation of MS base frame for Outdoor units complete with epoxy painting, vibration isolation pads, supports, hangers, railing, brackets etc.</b>  |                          |        |               |                  |        |                |                           |
| a        | 1.0TR Hiwall unit 3 Star rated   | Nos.                     | 1.00   |               | -                | 18.00% | -              | -                         |
| b        | 1.5TR Hiwall unit 3 Star rated   | Nos.                     | 17.00  |               | -                | 18.00% | -              | -                         |
| 5        | <b>Drain Piping</b><br>Supply and installation of drain piping PVC hard pipes, fitting, accessories, bends, elbows, tees, flanges, tappings, wall sleeves, hangers, supports, anchors.   |                          |        |               |                  |        |                |                           |
| a        | Supply and installation of drain piping PVC hard pipes, fitting, accessories, bends, elbows, tees, flanges, tappings, wall sleeves, hangers, supports, anchors.  | Rmt.                     | 230.00 |               | -                | 18.00% | -              | -                         |
|          | <b>TOTAL FOR INSTALLATION AMOUNT (B) (ALL ENCLUSIVE GST @18%)</b>  |                          |        |               | -                |        | -              | -                         |
|          | <b>GRAND TOTAL (A+B) Rs.</b>   |                          |        |               | -                |        | -              | -                         |
|          | <b>Say,</b>  |                          |        |               | -                |        | -              | -                         |

**Note:-**

- 1) All the rates shall be included of electricity supply & Water supply required for execution of work.
- 2) Exclusion: Any kind of civil works / carpentry works / temporary electrical supply / main electrical supply.
- 3) All the Taxes shall be included all taxes.
- 4) Warranty: Equipment to be supplied by us, are warranted for a period of 12 months from the date of handover.
- 5) Warranty: Compressor warranty for a period of 5 Years from the date of handover.